

INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS
SOUTHERN REGIONAL CENTRE, BANGALORE

SCHEDULE - 'B'

Name of work: Construction of platform, shifting & placing of Idols on the platform in the main hall area at IGNCA SRC, Bangalore.

Item No.	Description	Unit	Qty	Rate	
				In figures	In words
1.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable materials and disposal unserviceable material within 50metres lead	Sqm.	23.00		
2.	Dismantling the old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	Sqm.	39.00		
3.	Providing and laying in positiin cement concrete of speceified grade excluding the cost of centering and shuttering - All work up to plinth level - 1:3:6 (1Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal)	Cum.	2.00		

Prof. S.Settar
Director (Hon.)
IGNCASRC, Bangalore

Item No.	Description	Unit	Qty	Rate	
				In figures	In words
4.	Brick work with modular bricks of class designation 75 in foundation and plinth in: cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	7.50		
5.	15mm cement plaster of mix: 1:4 (1cement : 4 coarse sand)	Sqm.	26.00		
6.	Kota stone slab flooring over 20mm thick base (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm.	10.50		
7.	Extra for pre finished nosing in treads of plat form polished granite stone slab	Rmt.	79.00		
8.	Providing and fixing plished granite slab for flooring, black colour, 20mm thick over 20mm (average) thick base laid over and jointed with grey cement slurry with pigment to match the shade with base cement 1:4 (1cement : 4 coarse sand) etc., complete	Sqm.	19.40		

Prof. S.Settar
Director (Hon.)
IGNCASRC, Bangalore

Item No.	Description	Unit	Qty	Rate	
				In figures	In words
9.	Providing and fixing polished granite stone slab, black colour, 20mm thick in risers of steps, skirting, dado and pillars laid in 12mm (average) thick cement mortar 1:3 (1 cement 3 coarse sand and joined with grey/white cement slurry mixed with pigment to match the shade of slab etc., complete.	Sqm.	27.70		
10.	Labour charges for shifting Idols, made out of stone, placed on the platforms manually (by tripod chain pully) without damaging the Idols/flooring/structure of the building to the place as directed by officer/Engineer - in - charge.	No.	22.00		

Prof. S.Settar
Director (Hon.)
IGNCASRC, Bangalore